

ALLOW A MINIMUM OF 48 HOURS FOR CONCRETE
TO SET BEFORE BACKFILLING

BACKFILL WITH NATIVE SOIL OR EQUIV., FREE OF
LARGE ROCKS AND DEBRIS 3" DIA. OR LARGER,
MECHANICALLY COMPACTED IN 12" MAX. LIFTS.

